LEGEND - TREES All measurements are approximate & noted in meters.

No.	Species (Botanic Name)	Common Name	Height	Spread	Stems	Stem Diameter
1	Fraxinus excelsior	Common Ash	8-10	6-8	1	.25
2	Fraxinus excelsior	Common Ash	8-10	4-6	1	.2
3	Betula pendula	Silver Birch	6-8	3-5	1	.15
4	Fraxinus excelsior	Common Ash	6-8	4-6	1	.15
5	Fraxinus excelsior	Common Ash	6-8	4-6	1	.2
6	Betula pendula	Silver Birch	6-8	3-5	1	.15
7	Fraxinus excelsior	Common Ash	8-10	6-8	1	.25
8	Fraxinus excelsior	Common Ash	8-10	6-8	1	.20
9	Crataegus monogyna	Hawthorne	4-6	4-6	1	.1
10	Fraxinus excelsior	Common Ash	6-8	4-6	1	.2
11	Fraxinus excelsior	Common Ash	6-8	4-6	1	.15
12	Fraxinus excelsior	Common Ash	10-12	8-10	5	.3
13	Fraxinus excelsior	Common Ash	8-10	6-8	1	.3
14	Samucus nigra	Common Elder	4-6	6-8	7	.2/.3
15	Crataegus monogyna	Hawthorne	5-6	4-6	1	.2
16	Crataegus monogyna	Hawthorne	5-6	3-4	3	.15

LEGEND - GROUPS NOT INDIVIDUALLY SURVEYED

Group 1	Treed Hedge Line				
Cupressocyparis leylandii	Leylandii	8-10	4-6	1	.15
Group 2	Treed Hedge Line	8-10	4-6	1	.15
Cupressocyparis leylandii	Leylandii				
Group 3	Hedgerow	Variing heights, spreads & girths			
Crataegus monogyna	Hawthorne				
Group 4	Hedgerow	Variing heights, spreads & girths			
Crataegus monogyna	Hawthorne				
Group 5	Hedgerow	Variing heights, spreads & girths			
Crataegus monogyna	Hawthorne				

NOTE - ALL TRESS IN GROUPS 3-5 ARE IN POOR CONDITION DUE TO NEGLECT & LACK OF ANY BASIC HUSBANDRY.

ANTHONY JOHNS NDH
LANDSCAPE DESIGN LTD

The Clay,
Ballinclea, Donard,
Co. Wicklow, Ireland.

Tel: 087 2869180
E Mail: aj@anthonyjohns.com
Web: www.anthonyjohns.com

PROJECT
148 UNIT RESIDENTIAL MIXED HOUSING DEVELOPMENT

PROJECT ADDRESS
PUTTAGHAN LANDS,
ARDEN,
TULLAMORE,
CO.OFFALY.

CLIENT
JOHN FLANNAGAN DEVELOPMENTS LTD

DRAWING TITLE
TREE SURVEY

DWG NO. FLA-WEL/TS/001a

SCALE 1:1000 @ A3

DRAWN AJ **CHECKED** RM

DATE 6.9.22 **REF** DR

All measurements to be checked on site.
All areas refer to Bill of Quantities.